

Made possible



FLOOD RESPONSE CHECKLIST

PROPERTY RISK SOLUTIONS


TECHNICAL GUIDE

Flood Response Checklist

Take time before hand to evaluate when the pre-flood season activities should take place and also the realistic time needed to carry out the listed activities when flood is imminent, this will guide you in initiating these activities at the proper time.

PRIOR TO FLOOD SEASON EACH YEAR	Date to be completed by	Done
Review the site's pre-prepared Flood Emergency Plan. (Include possible external exposures such as neighbouring facilities or access / egress issues during the flood).	/ /	<input type="checkbox"/>
Ensure local flood area protections are in good condition - e.g. walk river banks berm, walls, levees, bridges and ensure these are in good condition and properly maintained.	/ /	<input type="checkbox"/>
Check that local culverts, bridges and onsite drainage systems are unobstructed.	/ /	<input type="checkbox"/>
Check condition of onsite flood protection features and equipment (including hand operated valves which may have seized or rusted & water removal equipment such as sump pumps). Make sure installation procedures are well practised.	/ /	<input type="checkbox"/>
Check availability of sandbags and essential back up equipment such as diesel generators. Also check tarpaulins and blankets are in good supply and condition. List the priority areas for protection and ensure the basics such as proper construction of sandbag walls are well practiced.	/ /	<input type="checkbox"/>
Ensure all members of flood emergency team are fully briefed and each knowledgeable of their duties and responsibilities.	/ /	<input type="checkbox"/>

BEFORE THE FLOOD - ON ALERT OF IMMINENT FLOOD CONDITIONS	Time needed	Done
Assign a person to monitor flood conditions and local conditions from government agencies, local authorities and onsite. Ensure this person has direct communication access to senior management, operations team and the flood response team.		<input type="checkbox"/>
Ensure sandbags are available and ready to be deployed.		<input type="checkbox"/>
Ensure flood doors and shields are installed at predefined locations.		<input type="checkbox"/>
Check sump pumps and water removal equipment are ready, fuelled, and operational.		<input type="checkbox"/>
Cover large stationary machinery and make sure they are anchored securely.		<input type="checkbox"/>
Shut down gas and flammable liquid pipelines.		<input type="checkbox"/>
Shut down key electrical supplies to minimise the threat of fire.		<input type="checkbox"/>
Relocate to safe areas or higher place: <ul style="list-style-type: none">On-floor storage in warehouse and yardOn-floor equipmentVehicles - cars, trailers, tractorsWater sensitive materials and equipment - such as drawing stores, files records, computer storage.		<input type="checkbox"/>



BEFORE THE FLOOD - ON ALERT OF IMMINENT FLOOD CONDITIONS	Time needed	Done
Anchor outdoor tanks or fill them with water or product to prevent them from floating away. Ensure vent lines on active tanks are extended above maximum anticipated water level.		<input type="checkbox"/>
Provide barricades for critical external equipment to prevent damage from floating debris.		<input type="checkbox"/>
Lash down portable containers of flammable or combustible liquids.		<input type="checkbox"/>
Check roof, yard and floor drains to ensure they are clear. Check throughout flood emergency that they are free from debris and blockages.		<input type="checkbox"/>
Check that backflow preventers on drains are operational to prevent back flow through drains.		<input type="checkbox"/>
Ensure salvage crew fully staffed, on alert and equipped to take action.		<input type="checkbox"/>
Put contractors and equipment suppliers on alert (e.g. emergency diesel hire companies).		<input type="checkbox"/>
Consider adequacy of security and surveillance and increase if necessary.		<input type="checkbox"/>
Ensure the ability to maintain fire protection systems and that they are all in an operational state during the flood emergency e.g. install barriers around sprinkler risers and safeguard foam supplies.		<input type="checkbox"/>

AFTER THE FLOOD - ACTIONS IMMEDIATELY AFTER THE FLOOD	Time needed	Done
Convene a meeting to coordinate action and salvage operations. Assess repair requirements, resources and business resumption plans / activities.		<input type="checkbox"/>
Check structural integrity and stability of all buildings and structures.		<input type="checkbox"/>
Check and assess all potential contamination situations and conditions. Make plans to clear up before other work begins.		<input type="checkbox"/>
Remove ponding and standing water onsite.		<input type="checkbox"/>
Clean and dry sensitive equipment - these should have been identified for priority treatment in the emergency plan.		<input type="checkbox"/>
Deploy specialist team to safeguard and make good electrical equipment's and distribution systems.		<input type="checkbox"/>
Begin de-humidifying operations. Dry wet building structures, materials and insulations.		<input type="checkbox"/>
Ensure good workflow in the removal of wet debris and damaged material.		<input type="checkbox"/>
Ensure all fire protection systems such as sprinkler systems are operational and continue to be so.		<input type="checkbox"/>
Ensure all site safeguards are invoked, such as permit systems and contractor control.		<input type="checkbox"/>
Check the condition of local structures that may have been affected or damaged by the flood e.g. blocked culverts, drains, bridges, overhead electrical systems, substations.		<input type="checkbox"/>
Maintain good communication channels to all working parties and ensure all works are coordinated.		<input type="checkbox"/>